

TABULATION OF CONCRETE & SIGNS								
PAY ITEM NO.		Curb and Gutter Type 2	Median Cover Material (Concrete) (4") (Colored)	36" Curb Drain (Special)	Concrete Footing (Type 3)	Fabricated Steel and Rustic Wood Sign	Relocate Sign	Notes
Station/Offset	Side							
11+23 to 13+90	MEDIAN		202					
14+75 to 16+62	MEDIAN	10	189					
10+80 to 14+72	RT	600						Planting Bed A, SE corner
14+10 to 15+23	RT	300						Planting Bed B, NE corner
10+92	RT			1				
12+52	RT			1				
21+10	LT				2	1		City of Rifle Sign
21+60	LT						1	Blue "GAS" Service Sign
TOTALS		910	391	2	2	1	1	
14+41 to 14+37	LT	68						Planting Bed C, SW corner

TEMPORARY TRAFFIC CONTROL SIGN TABULATION			
Sign Text	Sign Code	Dimensions	Quantity
Road Work Ahead	W 20-1	36 x 36	3
Left Lane Closed Ahead	W20-5(L)	36 x 36	3
Right Lane Closed Ahead	W20-5(R)	36 x 36	1
Left Shoulder Closed Ahead	W21-5a(L)	36 x 36	1
Right Shoulder Closed Ahead	W21-5a(R)	36 x 36	2
1500FT	W16-2aP	36 x 36	3
Begin Fines Double In Work Zone	R52-6a	24 x 36	3
Speed Limit 30	R52-1(30)	24 x 36	3
Merge Left Symbol	W4-2(L)	36 x 36	2
Merge Right Symbol	W4-2(R)	36 x 36	2
End Fines Double In Work Zone	R52-6b	24 x 36	2
TOTALS			25

TABULATION OF TRAFFIC CONTROL					
PAY ITEM NO.	Traffic Control Inspection	Traffic Control Management	Construction Traffic Sign (Panel Size A)	Drum Channelizing Device	Traffic Cone
	DAY	DAY	EA	EA	EA
	10	10	25	20	50
TOTALS	10	10	25	20	50

TABULATION OF SEEDING & CONDITIONING												
PAY ITEM NO.		Topsoil (Imported)	Seeding Type 1 (Native)	Seeding Type 2 (Native)	Soil Conditioning (Seed)	Soil Conditioning (Sod & Bed)	Sod	Mulching (Weed Free Hay)	Mulch Tackifier	Soil Retention Blanket (Straw-Coconut) (Biodegradable)	Fertilizer	Notes
Station/Offset	Side											
10+07 to 10+71	RT						1,090					Sod behind curb
10+70 to 12+70	LT						1,390					Sod behind curb
10+70 to 14+06	LT						1,710					Sod behind sidewalk
20+50 to 23+70	RT		0.32	0.17	0.49			0.17	x		x	Seeding Area A, SE Corner
20+25 to 23+10	LT		0.11		0.32			0.00	x		x	Seeding Area B, NE corner
11+20 to 12+01	RT		0.01		0.01					60	x	Seeding Area C, East Slope under bridge
20+90 to 21+70	RT	29			0.00							Planting Bed A, SE corner
20+35 to 21+20	LT	26			0.00							Planting Bed B, NE corner
TOTALS		55	0.44	0.17	0.82	0.11	4,190	0.2	0	60	0	
14+06 to 14+33	LT	17										Planting Bed C, SW corner

TABULATION OF PLANTINGS									
PAY ITEM NO.		Deciduous Tree	Evergreen Tree (10 Foot) (Ball and Burlap)	Evergreen Shrub (5 Gallon Container)	Large/Medium Deciduous Shrub (5 Gallon Container)	Small Deciduous Shrub (5 Gallon Container)	Ornamental Grasses (5 Gallon Container)	Transplant Brush (with rootball)	Notes
Station/Offset	Side								
Planting Bed A	RT			6	60	14	35		
Planting Bed B	RT			9	67	27	25		
Seeding Area A	RT	3	6						
Seeding Area B	RT		1						
TOTALS		3	7	15	127	41	60	0	0
Planting Bed C	LT	3		6	36	10	20		

SEE IRRIGATION PLAN AND DETAIL SHEETS FOR IRRIGATION QUANTITIES

Print Date: 8/9/2021		Sheet Revisions				As Constructed		TABULATION TABLES - 2 OF 2		Project No.	
File Name: TABULATION TABLES 2.DWG		Date:	Comments	Init.		No Revisions:		Designer: TAR		NA	
Horiz. Scale: As Noted Vert. Scale: As Noted		8/10/2021	ADDENDUM 1	1		Revised:		Detailer: RBR		NA	
Unit Information Unit Leader Initials						Void:		Sheet Subset: NA		Subset Sheets: 5 of 24	
					202 Railroad Ave, Rifle, CO 81650 (970) 665-6559				Sheet Number		G05